
Shrink Building Lines

High production rate Shrink Bundling Module with printed film (30-35 p/min): Model ZEE + ZT-25.





OPERATION

This Shrink Bundling module is often installed after the cardboard tray-sheet Bundling machine, Stacking System or conveyor assembly that pre-bundles cans, bottles or rectangular-shaped jugs. It also shrink wraps individual product units.

Optional use of silk-screen printed film (plastic with marking), easy open system and/or multipack system.

TECHNICAL FEATURES

Shrink wraps with polyethylene film.

Electronic temperature control in the shrink wrap tunnel.

Manual controls and fully automatic operation.

Touch-screen used to adjust, modify or add new formats.

Electric panel with built-in air-conditioning system.

Top quality materials: BECKHOFF controller, servo drives and servomotors, FESTO pneumatic system, TELEMECANIQUE electrical devices.


PRODUCTS AND MARKET SECTORS

Shrink wraps individual products, such as asphalt roofing felt, boxes, trays with products, ice cream boxes, cookie boxes or pre-bundled cluster packs, with a Stacking system; rectangular jugs or pre-bundled briks, with the conveyor at a 90° angle and a pneumatic cylinder assembly.



Shrink Building Lines

High production rate Shrink Bundling Module with printed film (30-35 p/min): Model ZEE + ZT-25.



| Voltage | 220v or 380v. |
|--------------------------------|----------------|
| Total power | 48 Kw. |
| Maximum width of the product | 500 mm. |
| Maximum width of the film | 700 mm. |
| Total line weight | 2.300 Kg. |
| Air consumption | 100 l/min. |
| Air pressure Film thickness | 6 atm. |
| Film thickness | 50-100 microns |
| Production | 30-35 p/min. |



Polígono Industrial Comarca-2, calle B, N° 20 31191 Ezquiroz (Navarra)

Tel.: +34 948 303 005 Fax: +34 948 302 644 E-mail: zorpack@zorpack.com

www.zorpack.com